



PROJECT DESCRIPTION

1395.0 trench metres - 4 x 100 mm ducts placed by Directional Drill, In Ground Horizontal Jack and Bore 450 mm steel casing under CN Main line for 52.0 metres, 320 trench metres of trench excavation over existing buried cables, Tie ins to existing manholes.

Client

Bell Canada

Job Number

09057

Work Type

Communications and Fibre Optics

Location

Ontario

Role

General Contractor

Duration

Feb - Jun 2009

