

Edmonton Meter Move Program 2010

**PROJECT DESCRIPTION**

The scope of the work was to relocate existing residential and commercial inside gas meters to the exterior of building for reading purposes and as a safety upgrade to ATCO Gas' system. All work was within the City of Edmonton and Capital Region, which includes St. Albert, Sherwood Park, Fort Saskatchewan, as well as other surrounding towns. In total there were 1,611 moves completed. Somerville was responsible for contacting customers and making appointments, applying for and tracking locates/permits, completing all underground work so that the existing steel line could be transitioned to plastic and a new riser installed on the exterior of the house, and completing all associated downstream piping. The below ground work involved digging either by hand or with a mini-excavator and using trenchless technology (ie. torpedo or hole hog as well as directional drill) to run the line underground with minimal disturbance to the customer's yard. The gas line downstream of the meter was also piped to complete the moving of the gas meter. The properties were then repaired back to the same or better condition than before our work, which included such things as laying sod, pouring and finishing concrete or completing asphalt repairs.

Client

Atco Gas

Job Number

10501

Work Type

Distribution Pipeline

Location

Alberta

Role

General Contractor

