

Steel Mains Replacement (SMR) - Ritchie

**PROJECT DESCRIPTION**

Project is to replace existing steel mains and services in the Ritchie area of Edmonton. Area is primarily residential and some commercial buildings. Project involves installation of 3,675m of PE mains up to 2", 470m of PE mains between 3" and 4", and 440 services. New mains and services will primarily be installed by directional drilling. Also involved with the replacement of service lines is to move any existing inside gas meter to the outside of the building. Inside gas meter work will consist of primarily residential houses with 200 series meters, and commercial meters up to 2M rotary meters.

Client

ATCO Gas

Job Number

14505

Work Type

Distribution Pipeline

Location

Alberta

Role

Prime Contractor