

Westlock Steel Pipe Replacement

**PROJECT DESCRIPTION**

Project is to replace existing steel mains and services in Westlock. Area is primarily commercial buildings, with some residential and some townhouses and condominiums. Project required the installation of 1,900m of 3/4" PE, 900m of 2" PE, 950m of 3" PE, 1,650m of 4" PE, 50m of 6" PE, and 120 services. New mains and services will primarily be installed by directional drilling. Also involved with the replacement of service lines is to move any existing inside gas meter to the outside of the building. Inside gas meter work will consist of primarily residential houses with 200 series meters, and commercial meters up to 2M rotary meters.

Client

AltaGas Utilities Inc.

Job Number

15515

Work Type

Distribution Pipeline

Location

Alberta

Role

Prime Contractor