



PROJECT DESCRIPTION

Project is to replace existing plastic main and services in the Bragg Creek North area outside of Calgary. This includes the abandonment, relocation, and installation of mains, services and meters, through direct bury, insertion or trenchless installation including meter placement to an outside appropriate location. Includes exterior and interior piping, fittings, meters, regulators, coring and sealing of existing holes as required to relocate meter sets. Cleanup and restoration to take place to same or better condition. Area is primarily residential and involves installation of 795m of PE mains up to 6 and 11 services. New Mains and services will be primarily installed by directional drilling.

Client

ATCO Gas

Job Number

18520

Work Type

Distribution Pipeline

Location

Alberta

Role

Prime Contractor

