ATCO GAS STEEL MAINS REPLACEMENT PROGRAM (SMR) – MERIDIAN ST FEEDER 12 INCH

SOMERVILLE

PROJECT DESCRIPTION

Project is to install a new 12" gas distribution feeder pipeline along Meridian Street in the northeast part of Edmonton. Area is primarily rural, with the installation primarily in a boulevard. Project involves working in proximity to and crossing through several pipeline ROW's. There is a large ravine/creek crossing where the pipe will be installed by one continuous horizontal direction drill that is 430m long, utilizing a 220 size drill. Project involves installation of 880m of 12" PE and 430m of 12" Steel. PE pipe will be installed by open cut.

For over sixty years, we have leveraged innovation to connect communities. We remain committed to responsibly construct a clean, sustainable future. Somerville builds the infrastructure that makes energy reliably flow; from generation to generation.

Job Number: 21501
Role: Prime Contractor
Duration: April 26, 2021 to June 30, 2021

Client: ATCO Gas

Primary Work Type: Pipeline

Robert B. Somerville Co. Limited 13176 Dufferin Street, King City, Ontario, Canada L7B 1K5 tel: 905.833.3100 fax: 905.833.3111