



## PROJECT DESCRIPTION

As part of the WAT-FIN NPS12 replacement program for Imperial Oil in Ontario, an 841m HDD crossing in rock was completed that entered on the Imperial Oil right of way behind an existing tree farm, and exited in the Joe Sam's Park in between two baseball diamonds. The bore crossed under the Grindstone Creek and a main railway easement. The bore was completed using a 12 1/4" tricone bit on an 8" mud motor and reamed to a final hole size of 18" to allow pulling in of the NPS12 product pipeline. The bore was completed on schedule and with minimal disruption to existing structures and facilities.

For over sixty years, we have leveraged innovation to connect communities. We remain committed to responsibly construct a clean, sustainable future. Somerville builds the infrastructure that makes energy reliably flow; from generation to generation.

Job Number: 20702-20

Role: Prime Contractor

Duration: January 29, 2021 to February 27, 2021

Primary Work Type: Pipeline Construction

Other Work Type: Horizontal Directional Drilling