



PROJECT DESCRIPTION

As part of the WAT-FIN NPS12 pipeline replacement program for Imperial Oil in Ontario, a 943m HDD crossing through 100m of overburden and then through a shale rock formation under a major creek and road was completed, with minimal disruption and on schedule. The use of a 12 1/4" PDC bit on an 8" mud motor while using wireline steering completed the pilot on target. A final reamed hole of 18" using an HDX hole opener enabled the installation of the NPS 12 pipe with no issues.

For over sixty years, we have leveraged innovation to connect communities. We remain committed to responsibly construct a clean, sustainable future. Somerville builds the infrastructure that makes energy reliably flow; from generation to generation.

Job Number: 20702-50

Role: Prime Contractor

Duration: March 1, 2021 to March 27, 2021

Client: Imperial Oil

Primary Work Type: Pipeline Construction

Other Work Type: Horizontal Directional Drilling